

**NERAVY COMMUNE PANCHAYAT**

**Name of work** :Providing Cement Concrete road and drain in Perumal koil north street at Neravy.

Sl No	Code No	Description of item	Quantity	Per	Rate		Amount
					In figure	In Words	
1	2.8.1	Earth work in excavation in foundation trenches or drains (Not exceeding 1.5m in width or 10sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m - all kinds of soil.	124.00 m <sup>3</sup>	1 Cum (one cubic metre)			
2	2.28	Supplying and filling in plinth with river sand under floors including, watering, ramming consolidating and dressing complete.	79.00 m <sup>3</sup>	1 Cum (one cubic metre)			
3	4.5.10	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all works upto plinth level 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40mm nominal size)	118.50 m <sup>3</sup>	1 Cum (one cubic metre)			
4	6.1.8	Brick work with bricks of class designation 35 in foundation and plinth in cement mortar 1:4 (1 cement : 4 sand)	37.00 m <sup>3</sup>	1 Cum (one cubic metre)			
5	6.18.4	Half Brick masonry with bricks of class designation 35 in foundation and plinth in cement mortar 1:4 (1 cement : 4 sand)	74.00 m <sup>2</sup>	1 Sqm (one square metre)			
6	4.9.2	Centering, shuttering including strutting, propping etc., and removal of form work for - retaining walls, return walls, walls (any thickness) including attached pillars, buttresses plinth and string courses, fillets etc.,	271.00 m <sup>2</sup>	1 Sqm (one square metre)			

7	<b>4.6.5</b>	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sill, fillets etc., upto floor five level, excluding the cost of centering, shuttering and finishing - 1:3:6 (1 cement : 3 sand : graded stone aggregate 20mm nominal size).	84.50 m <sup>3</sup>	1 Cum (one cubic metre)		
8	<b>4.5.4</b>	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size).	60.50 m <sup>3</sup>	1 Cum (one cubic metre)		
9	<b>13.24.1</b>	6 mm cement plaster of mix 1:3 ( 1 cement : 3 fine sand)	160.00 m <sup>2</sup>	1 Sqm (one square metre)		
10	<b>13.8.2</b>	12 mm cement plaster of mix 1:4 ( 1 cement : 4 fine sand)	336.00 m <sup>2</sup>	1 Sqm (one square metre)		
11	<b>14.33</b>	Pumping out water caused by springs, tidal or river seepage broken water mains or drains and the like.	150.00 kl	1 Kg (one Kilo litre)		